



Corrigendum to Bid – Documents-for-P.Way-Maintenance-Package 2

Name of the work: Maintenance of Permanent Way/Track works and associated assets and Restoration activities during breakdown in Station Yards and Mid-Section of the KRCL Project Line between (KM: 68/00 to KM: KAPT 0 Point) including BMPE Yard, VRJN-VKT, VRJN-KMLP and VKT-KUMU Bypass line (Package-2) in the jurisdiction of Vijayawada Division as per the Procedure Outline in Indian Railway Permanent Way Manual (IRPWM) in force for a period of two years from 01.06.2026 to 31.05.2028

Bid No. KRCL/P. Way Maint./Package -2/KAPT-OBVP/2026, Dated: 03.04.2026.

CORRIGENDUM

The following modifications are made in the proposed Tender Document mentioned above.

Existing Condition	Revised Condition
Page No. 47, Name of the work	Page No. 47, Name of the work
Name of the work: Maintenance of P. Way/ Track works and associated assets and restoration activities during the breakdown in stations, yards and mid-section of the KRCL Project Line between Obulavaripalle (OBVP) KM 0/00 to Brahmanapalle (BMPE) KM 68/00 excluding BMPE station (Package – 1) in the jurisdiction of Vijayawada Division as per the procedure outlined in Indian Railway Permanent Way Manual (IRPWM) in force for a period of two years from 01.06.2026 to 31.05.2028.	Name of the work: Maintenance of Permanent Way/Track works and associated assets and Restoration activities during breakdown in Station Yards and Mid-Section of the KRCL Project Line between (KM: 68/00 to KM: KAPT 0 Point) including BMPE Yard, VRJN-VKT, VRJN-KMLP and VKT-KUMU Bypass line (Package-2) in the jurisdiction of Vijayawada Division as per the Procedure Outline in Indian Railway Permanent Way Manual (IRPWM) in force for a period of two years from 01.06.2026 to 31.05.2028
Page – 45, Schedule – D (Existing)	Page – 45, Schedule – D (Revised)
Item No. 2: Extra for running charges for item No. 1 (beyond 3000 KMs) and item 3 A	Item No. 2: Extra for running charges for item No. 1 (beyond 3000 KMs)
Page – 45, Schedule – C (Existing)	Page – 45, Schedule – C (Revised)
Item No. 1A: pre-fabricated moulds (Zircon washed) single shot crucible fitted with automatic tapping thimbles with all labour, materials including supply of portion, tools and plants, aligning of rails, placing & fixing of mould, npreheating, welding, mechanised trimming, grinding withprofile grinder (including riser), testing, marking, painting with one coat of high build epoxy paint (two pack conforming to RDSO specification no. M&C/PCN-111/88) on the welded area up to 10 cm on either side. The work is to be completed in all respects as per IRS: T-19-2012 with latest updates and in accordance with “RDSO Manual for Fusion Welding of Rails by Alumino Thermic Process with up-to-date correction Slips in free rails or 3/10/20 rail panels. The work to be done under supervision of trained welding supervisor and carried out by trained welder having valid competency certificate from RDSO/TPP, Lucknow. Ultrasonic testing of welded joints shall be paid separately under relevant items.	Item No. 1A: Alumino thermit welding of 60kg/52 kg rail joints or combination joints of 60kg/52kg rail by pre-heat (SKV) welding technique using compressed air petrol/LPG for preheating, three piece pre-fabricated moulds (Zircon washed) single shot crucible fitted with automatic tapping thimbles with all labour, materials including supply of portion, tools and plants, aligning of rails, placing & fixing of mould, preheating, welding, mechanised trimming, grinding with profile grinder (including riser), testing, marking, painting with one coat of high build epoxy paint (two pack conforming to RDSO specification no. M&C/PCN-111/88) on the welded area up to 10 cm on either side. The work is to be completed in all respects as per IRS: T-19-2012 with latest updates and in accordance with “RDSO Manual for Fusion Welding of Rails by Alumino Thermic Process with up-to-date correction Slips in free rails or 3/10/20 rail panels. The work to be done under supervision of trained welding supervisor and carried out by trained welder having valid competency certificate from RDSO/TPP, Lucknow. Ultrasonic testing of welded joints shall be paid separately under relevant items.
Page -26, Annexure- I, Para No. 3 (Existing)	Page -26, Annexure- I, Para No. 3 (Revised)
3. Bid Security for a sum of ₹15,70,300/- is paid vide DD No....., Date..... of Bank. DD in original is enclosed. Or, Bid	3. Bid Security for a sum of ₹11,99,500/- is paid vide DD No....., Date..... of Bank. DD in original is enclosed. Or, Bid Security for a sum of ₹11,99,500/- is paid through RTGS



KRISHNAPATNAM RAILWAY COMPANY LIMITED

Regd. office: 3rd Floor, Lekha Bhavan, South Central Railway, Opposite Secunderabad East Metro Station Secunderabad - 500025, Telangana, CIN NO. U45200TG2006PLC051378
E-mail: registerofficekrcl@gmail.com

Security for a sum of ₹15,70,300/- is paid through RTGS vide UTR reference No., Date..... A copy of the RTGS payment is placed in the sealed cover No. 2. Full value of the Earnest Money shall stand forfeited without prejudice to any other right or remedies in case my/our Tender is accepted and if:	vide UTR reference No., Date..... A copy of the RTGS payment is placed in the sealed cover No. 2. Full value of the Earnest Money shall stand forfeited without prejudice to any other right or remedies in case my/our Tender is accepted and if:
Page -33, Para No. 5.4.9 (Existing)	Page -33, Para No. 5.4.9 (Revised)
I/We-----do declare that in the event of failure of contemplated negotiations relating to Tender No.KRCL/ P. Way Maint./ Package – 1/KAPT-OBVP/2026 opened on - -----my original tender shall remain open for acceptance on its original terms and conditions.	I/We-----do declare that in the event of failure of contemplated negotiations relating to Tender No.KRCL/ P. Way Maint./ Package – 2/KAPT-OBVP/2026 opened on ----- -my original tender shall remain open for acceptance on its original terms and conditions

It is hereby advised that Bidder while submitting their proposal please take note of the modifications made and act accordingly.

Sd/-
Sr. Manager/F&A/Expert/KRCL